



Band Room	1	24ch x Audio I/O / Video I/O	→	FOH(Bantam)
		4ch x MADI		Down Stage
		2ch x INTERCOM		SM desk
		2 x AC POWER / legrand(32)(16)		Distribution board
Down Stage	2	8ch x SP(Passive)	→	Station SL
		24ch x Audio I/O / Video I/O		FOH(Bantam)
		2ch x INTERCOM		SM desk
		2 x AC POWER		Distribution board
Chorus Room	3	4ch x MADI / 4ch x MADI	→	Band Room/Chorus Room
		4ch x SP(Passive)		SM desk
		8ch x Audio I/O / Video in		FOH(Bantam)
		2ch x INTERCOM		SM desk
UP Stage	4	2 x AC POWER	→	Distribution board
		4ch x MADI		Down Stage
		4ch x SP(Passive)		SM desk
		24ch x Audio I/O		FOH(Bantam)
SM Desk Lower	5	2 x AC Powercon	→	Distribution board
		24ch(12in12out) x Audio		FOH(Bantam)
Station SL	6	4ch x SP(Active)	→	Band Room
		2ch x SP(Active)		Upper SRR, SLL
		2ch x SP(Active)		Down Stage
		2ch x SP(Passive)		Amp Rack Cable
Amp Rack	7	Legrand(32)	→	Distribution board
		4ch x AES/EBU		FOH(Bantam)
Ticket Box	8	4ch x Audio in	→	FOH(Bantam)
		4ch(2in2out) / 2ch x cat6		FOH(Bantam)
Gallery BOX	1-6	AC Power	→	Distribution board
		4ch x cat6		FOH(Network Hub)
		Audio out		FOH(Bantam)
Upper SR	1	4ch x Audio out	→	FOH(Bantam)
Upper SL	2	4 x AC Powercon		Distribution board
		4ch x Audio out		FOH(Bantam)
Upper SRR	3	4 x AC Powercon		Distribution board
		4ch(2in2out) x Audio		FOH(Bantam)
Upper SLL	4	2ch x SP(Active)		Station SL
		4ch(2in2out) x Audio		FOH(Bantam)
Upper Center	5	2ch x SP(Active)		Station SL
Main SR	1	4ch x Audio out / AC Powercon Antenna	→	SM desk cable
		2ch x SP(Active)		Amp rack Cable 1
		2ch x SP(Active)		Amp rack Cable 2
		2ch x SP(Active)		Amp rack Cable 3
Main UP SR	3	2ch x SP(Active)		Amp rack Cable 4
Main UP SL	4	2ch x SP(Active)		

SPACE111	
SOUND PLAN	
TITLE.	
DATE.	2020.04.30
SCALE.	A1=1/50 , A3=1/100, A4=1/200